

KEY NOTES:

- MN/DOT S.P.4010 2" ADJUSTING RINGS AS NEEDED [6" MIN. TO 12" MAX.]. SET EACH RING IN FULL BED OF MORTAR.
- 2 MN/DOT S.P.4010 STD. SHORT CONE SECTION.
- 3 12" TOP SECTION REQUIRED.
- 4 USE ONLY PRECAST SECTIONS. NO BRICK OR BLOCK
- 5 8" CAST IN-PLACE CONCRETE OR 6" PRECAST REINFORCED CONCRETE (64" MINIMUM OD)
- 6 CEMENT MORTAR ALL AROUND
- 7 LEAN CONCRETE TO BEAR AGAINST FIRM UNDISTURBED SOIL
- PROVIDE WATER TIGHT PIPE CONNECTIONS SEE DETAIL THIS SHEET
- 9 O-RING GASKET
- FOR CONNECTION TO EXISTING MH'S, CORE DRILL OPENING AND PROVIDE TYPE B WATER TIGHT CONNECTOR
- 11 6" SAND OR FOUNDATION MATERIAL
- 12 UNDISTURBED SOIL OR COMPACTED SUBGRADE

400 - STD. SANITARY SEWER MH 400 - Std San MH.dwg 6/2015

H:\Cad_Comn\Details Updated\0 - SAN SEWER\400 - Std San MH
PLATE NAME:



1700 W 98TH ST. BLOOMINGTON MN 55431 PHONE (952) 563-8700

400 - Std San MH

ENGINEERING DIVISION
PUBLIC WORKS DEPARTMENT

LAST REVISED: 6/15/2015 LAST REVISED BY: KBO